

TEST REPORT ON
26 GA. PBR PANELS
AT 5' 0" – 3' 9" PANEL SPANS
WITH SEALED 'N' SAFE™ THERMAL BLOCKS
IN ACCORDANCE WITH
ASTM E1646-95 (2003) & E1680-95 (2003)

TESTED FOR:
Sealed 'N' Safe
320 West 100 North
Ephraim, Utah 84627
Telephone: (435) 283-6550
Fax: (435) 283-8326

TESTED BY:
ENCON® Technology, Inc.
1216 North Lansing Avenue, Suite C
Tulsa, OK 74106
Telephone: (918) 492-5992
FAX: (866) 366-1543


TEST WITNESSED BY:
Bala Sockalingam, Ph.D., P.E.

TESTING DATES: December 16, 2009
REPORTING DATE: December 21, 2009
ENCON® Project C1679-1



TABLE OF CONTENTS

	Page Number
SECTION I TEST SUMMARY	
1.1 Summary	1
1.2 Panel System Description	1
1.3 Test Results	1-2
1.4 Test Panel	3
SECTION II DESCRIPTION OF TEST	
2.1 Description of Test	4-5
SECTION III TEST RESULTS	
3.1 Specimen Identification	6
3.2 Test Data	7
SECTION IV TEST PHOTOGRAPHS	
4.1 Test Photographs	8-11
SECTION V APPENDIX	
5.1 Test Drawings	12-13
5.2 Flowmeter Calibration Chart	14
5.3 Test Conditions	15-16



SECTION I
TEST SUMMARY

TEST SUMMARY

1.1 SUMMARY

Tests were conducted on PBR metal roof panels at ENCON[®] Technology, Inc.'s Test Facility, Tulsa, Oklahoma. The purpose of the tests was to determine the resistance of exterior metal roof panel system with sealant to water penetration and air infiltration resulting from static air pressure difference between the exterior and interior surfaces. These tests meet the provisions of ASTM E1680-95 (2003) "*Standard Test Method for Rate of Air Leakage Through Exterior Metal Roof Panel Systems*" and ASTM E1646-95 (2003) "*Standard Test Method for Water Penetration of Exterior Metal Roof Panel Systems by Uniform Static Air Pressure Difference*".

The above-defined tests were witnessed by Bala Sockalingam, Ph.D., P.E., of ENCON Technology. The panels were installed on December 7, 2009 and tested on December 16, 2009.

1.2 PANEL SYSTEM DESCRIPTION

The tests were conducted on PBR panels which were 26 ga., 1-1/4" high and 36" wide through fastened panels. Each panel consisted of four major ribs spaced at 12" o.c. as shown on Page 3.

Sealant used in the panel sidelaps was Schnee Morehead Tacky Tape. The nominal size of the mastic tape sealant was 1/2" wide and 1/16" thick.


The panels were attached to nominal 16 ga. (0.06") Cee supports through the 4" thick blanket insulation, Sealed 'N' Safe[™] thermal block and 3" thick blanket insulation with #12 x 2" long hex head self-drilling screws with washers. Each panel spanned over unequal spans of 5' 0" and 3' 9". The sidelap fasteners were 1/4"-14 x 7/8" long hex head self-drilling screws with washers and were spaced at 12" o.c.

Sealed 'N' Safe[™] thermal blocks consisted of two 24 ga. steel plates with polyurethane foam injected between the plates to form a 1" thick block. The length and width of these thermal blocks were 72" and 5", respectively. The blocks were fastened to the supports through 3" thick blanket insulation with #12 x 1-5/8" long pancake head self-drilling screws located at each end of the blocks.

1.3 TEST RESULTS

The panel system was preloaded for positive load of 20 psf and negative load of 22 psf. The panel sidelaps were sealed to measure the extraneous leakage of the test chamber and test specimen perimeter. The panel sidelaps were unsealed and the air leakage rates were then measured for static positive pressure difference of 1.57 and 6.24 psf. Upon completion of the air leakage test, the panel system was uniformly sprayed with water at a rate of 5.0 gal/ft² per hour for 15 minutes at a static positive (inward) pressure difference of 12.0 psf. The results for the two tests are summarized on Page 2.

© ENCON 2009



CLIP SECTION VIEW

TEST METHOD: ASTM E 1680-95

TEST NO.	STATIC PRESSURE DIFFERENCE (PSF)	AIR INFILTRATION RATE	
		(cfm/ft ²)	(cfm/lin.ft)
1	1.57	0.0008	0.0024
2	6.24	0.0013	0.0040


TEST METHOD: ASTM E 1646-95

TEST NO.	STATIC PRESSURE DIFFERENCE (PSF)	WATER INFILTRATION
1	12.0	NO WATER LEAKAGE


NOTES:

1. 26 GA. PBR PANELS USED IN THESE TESTS.
2. PANELS WERE ATTACHED TO PURLINS WITH #12 X 2" LONG SDS @ 12" O.C.
3. SIDELAP FASTENERS WERE 1/4"-14 X 7/8" LONG SDS @ 12" O.C.
4. PANELS SPANNED TWO UNEQUAL SPANS OF 5' 0" AND 3' 9".
5. SIDELAP SEALANT WAS SCHNEE MOREHEAD TACKY TAPE (1/2" WIDE X 1/16" THICK).


© ENCON 2009



26 GA., PBR PANEL



FASTENER PATTERN



SEALED 'N' SAFE THERMAL BLOCKS

SECTION II
DESCRIPTION OF TEST

DESCRIPTION OF TEST

2.1 DESCRIPTION OF TEST

OBJECTIVES

The purpose of the tests was to determine the resistance of metal roof panel systems to water penetration and air infiltration resulting from static air pressure difference between the exterior and interior surfaces. The test method consisted of the following:

1. assembling the test panel in the test chamber to form a typical roof construction;
2. measuring the air leakage through the panel sidelaps and extraneous leakage of the test chambers;
3. spraying the exterior roof surface with water to determine any water penetration through panel sidelaps

TEST CHAMBER

The test chamber consisted of a box as shown in the applicable drawings in Section V. It contains one open surface against which the test specimen was installed. One static pressure tap is located at a corner to measure the chamber pressure in such a manner that the reading was not affected by the velocity of the air supply to or from the chamber or other air movement. The air supply opening into the chamber was arranged so that the air does not impinge directly on the test specimen with significant velocity.

AIR SYSTEM

The compressed air supply consists of a compressor unit capable of maintaining a constant positive or negative air pressure difference for the required test period. A digital manometer was used to measure the test pressure difference with accuracy of 1/100".

AIR FLOW METERING SYSTEM

A laminar flow element capable of measuring airflow of 40 SCFM was used to measure the air leakage through the panel sidelaps and extraneous leakage of the test chambers. The flow was measured as a differential pressure using a digital manometer and converted to actual flow using regression equation shown on the flowmeter calibration chart.

WATER SPRAY SYSTEM

The water spray system consists of equally spaced nozzles located at a uniform distance from the test specimen. The system was calibrated to deliver a minimum rate of 5.0 gal/ft² per hour.

CALIBRATION

The water spray was calibrated on October 6, 2009 and the air-flow measuring system was calibrated on August 10, 2009.

DESCRIPTION OF TEST

TEST SPECIMEN

The overall dimension of the test construction was in excess of 7' 9" x 8' 9". The panels covered unequal spans of 5' 0" and 3' 9". The construction width contained two full panels and two partial panels. The panels were attached to nominal 16 ga. Cee supports through the 4" thick blanket insulation, Sealed 'N' Safe™ thermal block and 3" thick blanket insulation with #12 x 2" long hex head self-drilling screws with washers. The panels were attached to 16 ga. eave, rake and ridge sections with self-drilling screws.

An overflow device that provided a 1/2" to 3/4" deep water pond was installed on one end of the test specimen. The perimeter of the test construction was sealed to the test chamber wall. The perimeter seals between the panels and the test chamber did not duplicate the actual building perimeter details. The details of the methods of construction are depicted in the enclosed test drawings in Section V.

TEST PROCEDURE

Since the panels were through fastened, no thermal movement of the panel to the support was conducted.

The test specimen was preloaded to a positive load greater than or equal to 15 psf or 75% of the building live load or 50 % of the design positive wind pressure difference. The test specimen was also preloaded to a negative load greater than or equal to 50 % of the building design wind uplift pressure difference.

The panel sidelap was temporarily sealed to measure the extraneous air leakage, Q_L , of the test chamber for the specified test pressure difference across the test specimen. The temporary sidelap seal was removed and the airflow through the sidelaps was measured after the test conditions were stabilized for the specified test pressure difference across the test specimen. This measured airflow was designated the total metered airflow, Q_M . The air leakage, Q , through the test specimen was equal to $Q_M - Q_L$. The ambient room temperature at the test specimen was also measured.

Upon the completion of the air leakage test, the water spray system was installed over the test specimen. The test specimen was subjected to the specified positive (inward) test pressure difference for 15 minutes while the spray system delivered water on the test specimen at a rate of 5.0 gal/ft² per hour. The depth and the temperature of the ponded water on the test surface were measured. The test specimen was observed for possible water leakage.

SECTION III
TEST RESULTS

TEST RESULTS

3.1 SPECIMEN IDENTIFICATION

Panel Manufacturer: CO Building Systems, Inc.

Model Type: PBR Panel

Dimensions: 36" wide with 1.25" high major ribs at 12" o.c.

Panel Gauge: 26 ga.

Panel Fasteners: #12 x 2" long hex head self-drilling screws with washers (DB Building Fasteners, Inc.)

Sidelap Fasteners: 1/4"-14 x 7/8" long hex head self-drilling screws with washers

Sidelap Fasteners Spacing: 12" o.c.

Thermal Blocks: Sealed 'N' Safe™ - consisted of two 24 ga. steel plates with polyurethane foam injected between the plates to form a 1" thick block. The length and width of the thermal block were 72" and 5", respectively. Polyurethane foam was manufactured by Utah Foam and designated as X10324.

Thermal Blocks Fasteners: #12 x 1-5/8" long pancake head self-drilling screws (DB Building Fasteners, Inc.)

Insulation: 4" thick and 3" thick blanket insulation

Support Thickness: 16 ga. (0.059")

Sealant Manufacturers: Schnee Morehead

Panel Sealant: Tacky Tape (nom. 1/2" wide x 1/16" thick)

Note: All the test materials were supplied by CO Building Systems, Inc. and Sealed 'N' Safe and were not sampled by ENCON.

TEST RESULTS

3.2 TEST DATA

Date: 12.16.09
 Panel Manufacturer: CO Building Systems
 Panel Type: PBR
 Panel Gauge: 26
 Panel Width (in): 36
 Panel Attachment: #12 x 2" long through 4" thick insulation, Sealed 'N' Safe™ thermal block and 3" thick insulation
 Sealant Manufacturer: Schnee Morehead Tacky Tape
 Panel Sealant: 1/2" wide x 1/16" thick mastic tape
 Panel Span (ft): 5' 0" - 3' 9"
 Test Area (ft²): 67.8
 Preload Positive Pressure (psf): 20
 Preload Negative Pressure (psf): 22
 Ambient Temperature (F): 62
 Panel Temperature (F): 62
 Barometric Pressure (in. Hg): 29.71
 Water Depth (in): 0.625

Test Method: ASTM E1680-95 (2003)

Test No.	Static Pressure Difference psf	Initial Reading DP (in)	Initial Reading ¹ cfm	Final Reading DP (in)	Final Reading ¹ cfm	Total Air Leakage ² cfm	Air Infiltration Rate	
							cfm/ft ²	cfm/lin.ft
1	1.57	0.680	3.442	0.691	3.497	0.0552	0.0008	0.0024
2	6.24	2.173	10.963	2.191	11.053	0.0903	0.0013	0.0040

¹ The actual flow is calculated using the regression equation shown on the flowmeter calibration chart.

² Total Air Leakage $Q_{st} = Q \times (1.326 \times B / (0.075 \times (T + 460)))^{0.5}$

Test Method: ASTM E1646-95 (2003)

Test No.	Static Pressure Difference psf	Rate (gal/hr/ft ²)	Test Duration (min)	Water Infiltration
1	12.0	5	15	No Water Leakage

SECTION IV
PHOTOGRAPHS

PHOTOGRAPHS



PHOTO 1 View of sealant in the panel sidelap.
(DSC00029)




PHOTO 2 View of PBR panel and sidelap attachment.
(DSC00062)

PHOTOGRAPHS




PHOTO 3 View of test setup. The panel sidelaps were temporarily sealed for extraneous leakage measurement of the test chamber. (DSC00078)



PHOTO 4 View of the air flow measuring instruments. (DSC00079)

PHOTOGRAPHS



PHOTO 5 View of flow measurements at differential pressure of 1.57 psf (equivalent to 0.3" of water). (DSC00083)



PHOTO 6 View of flow measurements at differential pressure of 6.24 psf (equivalent to 1.20" of water). (DSC00082)

PHOTOGRAPHS




PHOTO 7 View of water spray test.
(DSC00085)



PHOTO 8 View of underside of the panel during the water test.
(DSC00089)

SECTION V
APPENDIX




SEALED 'N' SAFE THERMAL BLOCKS
TEST DETAILS

ASTM
E1646 & E1680


12/16

© ENCON 2009




1
1
PLAN VIEW

© ENCON 2009



1
2

SECTION VIEW A-A



1
3

SECTION VIEW B-B



15555 North 79th Place
Scottsdale, AZ 85260
Phone: (480) 948-3789
Fax: (480) 948-3610
www.flow-dynamics.com
sales@flow-dynamics.com

Calibration Report

Customer Name: Encon Technology, Inc Report # FCAL14552 - 784180-R1
Customer Address: 6717 South Yale Avenue Suite 200 Tulsa OK USA 74136
Customer PO # CC Received Date: 7/8/2009
Model # 50MW20-2 Cal Date: 7/15/2009
Serial # 784180-R1 Lab Temp: 75 Deg F
Signal: L.F.E. Lab Relative Humidity: 21%
Calibration Procedure: FDP-001
Calibration Tech: Keith Std. Temperature (Deg F) 70
Fluid Specifications: Air Std Pressure (PSIA): 14.7
Notes, Adjustments & Repairs STP: 70 Deg. F and 14.7 PSIA, Meter Pres. Measured Upstream

Calibration Results (As Found = As Left)

Test Point	Meter Pres	Delta P	Meter Temp	Act. Flow	Std. Flow	C Factor	K Factor	Viscosity
#	PSIA	In H2O @4C	Deg. F	ACFM	SCFM	Rho*dP/mu^2	Q*mu/dP	mP
1	14.651	8.45565	78.041	42.8259	42.0560	1.8180E-05	936.717	184.99
2	14.526	7.36231	77.433	37.7004	36.7475	1.5742E-05	946.149	184.81
3	14.413	6.43781	77.101	33.2558	32.1851	1.3682E-05	953.951	184.71
4	14.347	5.82296	76.905	30.2534	29.1558	1.2331E-05	959.156	184.65
5	14.268	5.00972	76.735	26.2149	25.1320	1.0560E-05	965.772	184.60
6	14.194	4.22053	76.778	22.2180	21.1883	8.8483E-06	971.642	184.61
7	14.135	3.53577	76.809	18.7187	17.7762	7.3809E-06	977.193	184.62
8	14.080	2.81703	76.805	14.9940	14.1833	5.8576E-06	982.446	184.62
9	14.026	2.06688	76.786	11.0652	10.4272	4.2817E-06	988.135	184.61
10	13.977	1.27519	76.788	6.85805	6.44001	2.6324E-06	992.653	184.61
11	13.946	0.70896	76.812	3.82914	3.58756	1.4601E-06	996.936	184.62
12	13.928	0.36702	76.925	1.98573	1.85771	7.5448E-07	998.849	184.65

Standards Used in Calibration

Standard #	Description	Serial #	ReCal Date
FDI-005	5 Cu. Ft. Bell, 1 cuft volumes	n/a	2/09/2010
FDI-120	Mensor, DPG Model 2104, SN: 531998	531998	6/04/2010
FDI-123	Small Bell Cart - mA, VDC, Frequency	n/a	2/23/2010
FDI-131	Digital Mensor 2101 Pres. Trans. - 125 PSIA	532107	5/12/2010
FDI-44	Digital Mensor Diff. Pres. Trans. - 10 "H2O	241130	11/4/2009

The instrument referenced above was calibrated using standards traceable to the National Institute of Standards and Technology. Calibration reports for references maintained by FDI are available upon request to the customer of this calibration report. The volumetric flowrates reported are within a best uncertainty of +/- 0.25% of reading. Flow Dynamics, Inc. calibration services are accredited by NVLAP to ISO/IEC 17025:2005 (NIST Handbook 150) and are compliant to ANSI/NCCL Z540-1-1994; Part 1.

The results reported relate only to the item(s) calibrated as described above. This report may not be reproduced, except in full, without the written approval of Flow Dynamics Inc.

I certify the accuracy of this Calibration Report:

Andrew Yee
Name

Calibration Engineer
Title

Andrew Yee

Signature

Digitally signed by Andrew Yee
DN: cn=Andrew Yee, o=Flow
Dynamics, ou=Calibration Lab,
email=ayee@flow-dynamics.com,
c=US
Date: 2009.07.15 13:56:48 -0700

End of Report



APPENDIX

5.3 TEST CONDITIONS

A. OWNERSHIP OF ENCON WORK PRODUCT

All test results developed as a part of this work shall be CUSTOMER's property. All samples submitted to ENCON for testing shall become the property of ENCON. CUSTOMER understands that any test program including procedures and test machines incorporated as a part of this work is a result of continuing long-term research and development by ENCON and because of this all ENCON test procedures, test drawings and other intellectual property relating to this work is and shall remain the property of ENCON. Test samples were disposed of shortly after completion of the tests unless other arrangements were agreed to in writing prior to the test.

ENCON will use its normal procedures to retain copies of the information developed as a part of this test for a period of three years from the date the work was done. This material may be routinely destroyed thereafter.

B. ENCON GUARANTEE

ENCON guarantees it used its best effort to accomplish this test work. Work done by ENCON was carefully completed by personnel believed to be competent. ENCON tests were based on what was currently believed to be good engineering practices in use at the time of the test.

The safety factors used are generally accepted as suitable to produce safe results. However, good engineering practices and applicable codes and insurance requirements must be taken into consideration in determining if a test procedure is satisfactory for a specific end use. Applicable specifications, good engineering practices and applicable safety factors may change in the future. CUSTOMER should be alert to these changes.

The information and test results presented by ENCON in this test report are offered in good faith based on information ENCON believes to be reliable. This information is offered as a guide to assist CUSTOMER in CUSTOMER's endeavors and does not contain any warranties as to fitness by ENCON. No REPRESENTATION OF WARRANTIES, EXPRESS OR IMPLIED, INCLUDING THOSE OF MERCHANTABILITY AND OF FITNESS FOR A PARTICULAR PURPOSE are made by ENCON, and more specifically, ENCON hereby expressly disclaim such. In no event shall ENCON be liable for ANY CONSEQUENTIAL, INCIDENTAL OR SPECIAL DAMAGES, including, without limitation, labor, transportation, loss of use, loss of profits, harm, personnel injury and damage to property.

If any doubt exists as to the proper means of interpreting or using the test results contained herein, contact ENCON for clarification. CUSTOMER should assure themselves through careful evaluations that test results are suitable for those end uses to which CUSTOMER intends to put them.

APPENDIX

Information and material provided by CUSTOMER to ENCON was reviewed by an ENCON executive. However, ENCON does not accept the responsibility for accuracy or verification of CUSTOMER's information or the suitability of CUSTOMER materials. Materials supplied by CUSTOMER were tested as received and were not evaluated for code or insurance compliance. CUSTOMER is expected to review the ENCON drawings, tables, test results and other information provided by ENCON to CUSTOMER critically so as to assure CUSTOMER that these presentations, formulas, drawings and other information are accurate and meaningful for the purpose intended.

No other warranties or guarantees shall be issued, implied, delivered or otherwise construed to be issued, implied or delivered.

ENCON® TECHNOLOGY, INC., 2009

